

## DAV Centenary Public School-Hanumangarh Junction

**Name of Work:- To connect school building from main gates through Interlocking roads.**

SR NO	Nomenclature	Appx Qty.	unit	Estimate ed rate i/c GST	Estimate d amount i/c GST
1	Preparation and consolidation of Subgrade with Power Road Roller of 8-12 Tonne Capacity after excavating/ filling earth to an average of 30 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc and re rolling the subgrade and disposal of surplus earth with lead upto 500 meters as per the instruction of Incharge.	1200.00	Sqm		
2	Supplying, laying, spreading and compacting Gravel / Tila sand in uniform thickness of 4 inches compacted and rolling with Power Road Roller of 8-12 Tonne Capacity in stages to proper grade and camber, watering and compacting to the required density.	1200.00	Sqm		
3	Supplying, laying, spreading and compacting Gravel / Tila sand in Berm in Average thickness of 3 inches along brick edging outside road area to proper grade and camber, watering and compacting to the required density.	650.00	Sqm		
4	Half brick masonry with common burnt clay F.P.S. (Non Modular) bricks of class designation 7.5 in foundation & plinth in Cement mortar 1 : 4 (1 cement : 4 coarse sand) along road edge including necessary excavation, dressing and disposal of surplus earth with lead upto 500 meters. The outer surface of brick wall shall be Plastered (appx 5" high and top of wall) in cement sand mortar 1:6 including racking of joint etc. complete with neat cement (punning).	200.00	Sqm		
5	Providing and Laying 80 mm thick factory made cement concrete interlocking paver block of M-40 Grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over 25mm thick sand underneath and filling joints with sand etc all complete as per the direction of Engineer Incharge.	1200.00	Sqm		
6	Providing and fixing Cement concrete cover of size 450 x 450mm with frame and necessary cement concrete 1:2:4 surrounding frame.	5.00	Nos		
7	Providing and fixing Cement concrete cover of size 600 x 600mm with frame and necessary cement concrete 1:2:4 surrounding frame.	5.00	Nos		
				<b>Total</b>	
	Add 5% for contingency				
	<b>Grand total</b>				

Principal

DAV Centenary Public School Hanumangarh Junction